



## Certificate of Analysis

### Permeance

Product Name	Streetbond SP-150
Batch Number	93937
Manufacture date	2/07/02
Sample prep date	Unknown - free films provided by manufacturer
Testing dates	3-21-02 to 3-29-02
Test Method	ASTM D1653 Standard test method for water vapor transmission of organic coating films, Method B (wet cup)
Test conditions	Per ASTM standard. Any deviation reported at end of certificate


This certificate confirms that the above product was tested as per standard specification using calibrated equipment and qualified staff. The following test results were obtained.

### RESULTS

Thickness (mils)	units	result
82	g/m <sup>2</sup> /hr	1.99
52	g/m <sup>2</sup> /hr	3.45

Note that the two results are fairly consistent when one takes into account the significant thickness variation. Thicker than normal samples were used to obtain a good seal.

Weldon Laboratories, Inc., Project J02024

  
Dwight G. Weldon, President